

VerTech™ Mobile Event Structures

VT Mobile™ 10-10 Stage



Essential Facts

Total frontage	15m (including decked pa wings)
Performance dimensions	10m wide x 10m deep
Decked PA wings	2.4m x 2.4m per side
Build time	3-4 hours (approx.)
Crew required to build	3 crew (provided by us)
PA facilities	Flown (up to 1 ton per side) or stacked on PA wing decks
Branding opportunities	Header banner, scrim and backdrop
Trim height	4.3m - stage floor to roof (underside of truss)
Stage build height	Min: 1m - Max. 1.5m (floor to stage deck)
Storage inside stage	Yes (e.g. FOS barrier, hoists, risers etc.) Subject to Qty
Plant	None required
Power to build the stage	Hydraulically powered (for stage build/load out only)
Doors to stage	3 (we provide 2 x sets of steps)
Opening side of stage	Nearside
Audience Guideline	1,000-6,000

Travelling Information

Length	17m
Height	4.1m
Width	2.5m
Weight	24,000kg



Your safe pair of hands in the event industry

Actavo Events
Killeen Road, Bluebell, Dublin 12, D12 KXE6 | +353 (1) 5055 888
eventsireland@actavo.com