### VerTech ™ Mobile Event Structures

## VT Mobile™ 10-08 Stage

# Actavo

#### **Essential Facts**

Total frontage	15m (including decked pa wings)
Performance dimensions	10m wide x 8m deep
Decked PA wings	2.4m x 2.4m per side
Build time	2-3 hours (approx.)
Crew required to build	2 crew ( provided by us)
PA facilities	Flown (up to 1 ton per side) or stacked on PA wing decks
Branding opportunities	Header banner, scrims and backdrop
Trim height	4.7 Sm – stage floor to roof
Stage build height	Min: 1m - Max. 1.5m (floor to stage deck)
Storage inside stage	Yes (e.g. FOS barrier, hoists, risers etc.) Subject to qty
Plant	None required
Power to build the stage	Hydraulically powered (for stage build/load out only)
Doors to stage	3 (we provide 2 x sets of steps)
Opening side of stage	Both
Audience Guideline	1,000-5,000

### **Travelling Information**

Length	17m
Height	4.1m
Width	2.9m
Weight	21,000kg

