

VerTech™ Mobile Event Structures

VT Mobile™ 10-08 Stage



Essential Facts

| | |
|--------------------------|--|
| Total frontage | 15m (including decked pa wings) |
| Performance dimensions | 10m wide x 8m deep |
| Decked PA wings | 2.4m x 2.4m per side |
| Build time | 2-3 hours (approx.) |
| Crew required to build | 2 crew (provided by us) |
| PA facilities | Flown (up to 1 ton per side) or stacked on PA wing decks |
| Branding opportunities | Header banner, scrim and backdrop |
| Trim height | 4.7 5m - stage floor to roof |
| Stage build height | Min: 1m - Max. 1.5m (floor to stage deck) |
| Storage inside stage | Yes (e.g. FOS barrier, hoists, risers etc.) Subject to qty |
| Plant | None required |
| Power to build the stage | Hydraulically powered (for stage build/load out only) |
| Doors to stage | 3 (we provide 2 x sets of steps) |
| Opening side of stage | Both |
| Audience Guideline | 1,000-5,000 |

Travelling Information

| | |
|--------|----------|
| Length | 17m |
| Height | 4.1m |
| Width | 2.9m |
| Weight | 21,000kg |

