

VerTech™ Mobile Event Structures

VT Mobile™ 15-12 Orbit Stage



Essential Facts

Total frontage	22.8m wide (including production areas)
Performance dimensions	15m wide x 12m deep
Build time	Stage without production areas: 9-10 hours Stage with production areas: Floor = 2 hours (this is usually built 1 day before the roof build) Roof = 8-9 hours (approx.)
Crew required to build	6 crew (provided by us)
PA Facilities	Flown (up to 2 ton per side)
Monitor Positions	Optional 3.8m x 3.8m Internal height 2.5m
Branding opportunities	Header banner, side scrim (in fills) & backdrop. Monitor positions can also be branded if used.
Trim height	7.6m
Stage build height	1.8m (approx.)
Storage inside stage	No
Plant	None required (uses in built hi-ab cranes)
Power to build the stage	Generator – provided by us (for stage build/load out only)
Doors to stage	4 (we provide 02 x sets of steps & 01 x ramp)
Opening side of stage	Both
Audience Guideline	5,000-15,000 people

Travelling Information

Length	21m
Height	4m
Width	2.5m
Weight	42,000kg



Your safe pair of hands in the event industry

Actavo Events
London Office | Wallingford Road, UB8 2XS | +44 (0) 1932 222 599
Scotland Office | 6 Muir Road, Houstoun Industrial Estate, Livingston, EH54 5DR | +44 (0) 131 285 4238
events.uk@actavo.com