

## VerTech™ Mobile Event Structures

# VT Mobile™ 15-12 Orbit Stage



### Essential Facts

<b>Total frontage</b>	22.8m wide (including production areas)
<b>Performance dimensions</b>	15m wide x 12m deep
<b>Build time</b>	Stage without production areas: 9-10 hours Stage with production areas: Floor = 2 hours (this is usually built 1 day before the roof build) Roof = 8-9 hours (approx.)
<b>Crew required to build</b>	6 crew (provided by us)
<b>PA Facilities</b>	Flown (up to 2 ton per side)
<b>Monitor Positions</b>	Optional 3.8m x 3.8m Internal height 2.5m
<b>Branding opportunities</b>	Header banner, side scrim (in fills) & backdrop. Monitor positions can also be branded if used.
<b>Trim height</b>	7.6m
<b>Stage build height</b>	1.8m (approx.)
<b>Storage inside stage</b>	No
<b>Plant</b>	None required (uses in built hi-ab cranes)
<b>Power to build the stage</b>	Generator - provided by us (for stage build/load out only)
<b>Doors to stage</b>	4 (we provide 02 x sets of steps & 01 x ramp)
<b>Opening side of stage</b>	Both
<b>Audience Guideline</b>	5,000-15,000 people

### Travelling Information

<b>Length</b>	21m
<b>Height</b>	4m
<b>Width</b>	2.5m
<b>Weight</b>	42,000kg



Your safe pair of hands in the event industry

Actavo Events  
Killeen Road, Bluebell, Dublin 12, D12 KXE6 | +353 (1) 5055 888  
eventsireland@actavo.com